



Chateau



Routed Slab Maple Door, Raised Panel Styling,
Solid Drawer Front, Reverse Bevel Edge Profile,
Maple Hardwood, Standard Overlay

Now Available In Stock

Features

Durable, Plywood Construction

Cabinet boxes are made using all plywood construction with a light maple interior.

Wide Range of Sizes

Variety of cabinet sizes in stock for multifamily kitchen and bath projects.

Soft-Close Doors

Standard 6-way adjustable hinges with soft-close feature to prevent slamming.

Soft-Close Drawers

Dovetail construction with steel undermount soft-close glides.

Available for Quick Ship

Locally stocked in our Braintree, MA warehouse for fast and convenient delivery.

Stock Color

Other colors are available via special order. See your sales rep for details.



NATURAL


All Plywood Construction



At a Glance


- Plywood construction
- 5/8" Nominal (16 mm) solid dovetail drawers with 1/4" Plywood Bottoms
- 3/4" Nominal (18 mm) plywood shelves with light maple laminate and matching PVC edge banding
- Laminate interior and exterior sides

Detailed Specifications




Adjustable Hinges

Heavy duty, self closing, and concealed within the cabinet door and frame. Soft close option available.




Drawer Sliders

75 lb load rated, epoxy coated slides. Upgrades to 100 lb full extensions and 75 lb undermount soft close full extension are available.




Solid Dovetail Drawers

5/8" featuring four sided construction and captive 1/4" Nominal (6.4 mm) matching plywood bottom.




Door and Drawer Fronts

Assembled with kiln-dried solid American hardwood.




Edgebanded Plywood Shelves

3/4" Nominal (18 mm) provide both a matching appearance with the interior of the cabinet, and improved water resistance.




Face Frame Stile and Rails

3/4" thick by 1 1/2" Nominal (18 mm by 38 mm) wide kiln-dried hardwood. Frames are assembled under pressure with pocket screws.




Wall and Base Backs

1/2" Nominal (12 mm) plywood with light maple laminate interior. Wall backs are stapled and glued into rabbeted ends.




Wall and Base Sides

1/2" Nominal (12 mm) plywood with light maple laminate interior and designated laminated exterior.




Base Bottoms

1/2" Nominal (12 mm) plywood with light maple laminate interiors. Bottoms are hot melt glued into dados on all four sides.




Wall Tops and Bottoms

1/2" Nominal (12 mm) plywood with light maple laminate, hot melt glued into dados on all four sides.



I-Beam Construction Rails

1/2" Nominal (12 mm) plywood. Rails are hot melt glued into face frame, sides, and cabinet back.



Standard Toe Kicks

Measure 3 1/2" deep by 4 1/2" tall. 9" universal access toe kick available on most cabinet models.



SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE.

© 2021 SMART CABINETRY® WWW.SMARTCABINETRY.COM 70680 COUNTY ROAD 23, NEW PARIS, INDIANA 46553
SC21_01 REV 21_08